

TABELA OBJĘTOŚCI ROBÓT ZIEMNYCH

Parking wewnętrzny

Pikietaż	Powierzchnia		Odległość	Objętość	
	Wykop	Nasyp		Wykop	Nasyp
km	m2	m2	m	m3	m3
0+000		82,934	0,000	0,000	
0+009		73,190	9,000		746,404
0+015,81		28,968	6,810		498,424
0+023		27,710	7,190		208,276
0+033		22,253	10,000		277,100
0+036,69	0,700	11,054	3,690	2,583	82,112
0+050,43	13,299		13,740	182,725	151,879
0+070	14,990		19,570	293,354	
0+088	1,768	3,226	18,000	31,824	1,613
0+088,5	1,740	7,734	0,500	0,870	1,613
0+105,5		19,878	17,000		131,474
0+106,5		34,179	1,000		19,878
0+127,1		54,375	20,600		704,082
0+140,85		43,875	13,750		747,656
0+142,1		37,279	1,250		54,844
0+160,0		32,736	17,900		667,290
0+173,91	2,189	16,016	13,910	30,449	455,361
					222,786
			Razem	541,805	4 970,791

Pas wyłączenia

Pikietaż	Powierzchnia		Odległość	Objętość	
	Wykop	Nasyp		Wykop	Nasyp
km	m2	m2	m	m3	m3
0+000	2,900		0,000		
0+013	2,190	0,980	13,000	37,700	21,560
0+035	2,250	1,340	22,000	48,180	29,480
0+038	2,250	1,900	3,000	6,750	4,020
0+057	1,350	0,300	19,000	42,750	81,225
0+062	0,920	1,100	5,000	6,750	1,500
0+069,66	0,200	0,600	7,660	7,047	8,426
				1,532	4,596
			Razem	150,709	150,807

Wjazd

Pikietaż	Powierzchnia		Odległość	Objętość	
	Wykop	Nasyp		Wykop	Nasyp
km	m2	m2	m	m3	m3
0+006,5	4,250	1,620	6,500	27,625	10,530
0+010	2,000	1,930	3,500	7,000	6,755
0+016,42	1,100	2,800	6,420	7,062	17,976
			Razem	41,687	35,261

Skarpa od strony rzeki Łyny

Powierzchnia		Odległość	Objętość	
Wykop	Nasyp		Wykop	Nasyp
m2	m2	m	m3	m3
	10,695	120		1283,4

Chodnik

Pikietaż	Powierzchnia		Odległość	Objętość	
	Wykop	Nasyp		Wykop	Nasyp
km	m2	m2	m	m3	m3
0+000					
0+010		0,240	10,000		2,400
0+020		0,570	10,000		5,700
0+030		0,840	10,000		8,400
0+040		1,080	10,000		10,800
0+057		1,380	17,000		23,460
0+071		2,730	14,000		38,220
0+082		2,730	11,000		30,030
0+085		2,880	3,000		8,640
0+089,87		2,580	4,870		12,565
			Razem		140,215

Suma Objętości	
Wykop	Nasyp
m3	m3
734,201	6 580,473